

Bond Testing Machine

This machine is designed to test the bond of various bushes after the moulding process. Attractive pneumatically operated machine which gives precise results, also provides proof load testing due to presence of pressure gauges.



> Features:

- Pneumatic Operated Testing Process
- Manual mode operation of testing
- Pneumatic Operated OK Marking system
- Accommodates different types of components up to 70 mm diameter.
- Glass mirror for Visual inspection with Light source.
- Pressure Gauge for proof load testing.
- Adjustable proof load.
- Optional Digital Load Indicator & Load Cell

Product Parameter:

Cylinder Size	Diameter150mm X Stroke75mm
Testing Capacity	1 Ton, 5 Ton
Electrical Power Supply	230V AC, 50Hz
Cubic Feet per Minute (CFM)	2

Website: <u>www.summitengineers.net</u> Email Id: <u>sales@summitengineers.net</u> Contact No: +91-9860556670